



OOSTENDE (BE) | RENTEL NV announces the landfall of its export cable in Zeebruges

The cable, with a length of 40 kilometers, will be placed within a dredged trench on the seabed by a cable laying vessel. A cable laying barge will take over in the shallow waters 6 kilometer before the coast and bring the cable ashore in Zeebruges. The installation of the last 450 meters of cable on the beach will be done by means of mobile cranes. Dredgers will fill the trench, thus burying the cable in the seabed. As from 1 km before the coast, a mechanical trenching machine on caterpillars will carry out these works. With the landfall of this export cable, Rentel will be the first windfarm connected to the new high voltage station "Stevin", in Zeebruges.